

## **Covenant Solar & Roofing**

### **Highland Presbyterian Church Flat Roof Estimate**

3/27/2023

All work to be performed per OSHA standards and manufacturers specifications

- Remove loose ballast to expose built up system
- Remove 2 layers of ½" fiberboard along with built up to expose concrete deck
- Install 1" polyisocyanurate board over entire roof surface with HDP concrete fasteners
- Install crickets against back wall and side area to force water flow to get to scuppers to drain as designed
- Mechanically attach 060 Mulehide TPO per manufacturer specifications over entire roof area
- Reuse copper flashing around perimeter
- Install T-bar around penetrations as needed
- Remove all debris and haul away
- Provide 20 year NDL warranty upon completion and once payment is made in full

**All above work to be completed for a price of \$55,428 Fifty five thousand four hundred twenty eight dollars**

Kevin Prince  
Senior Production Manager  
Covenant Solar and Roofing

**\*\*Please note, I know this job may not take place until summer, this will be subject to a slight increase (15% maximum) due to unforeseen material cost increases. If you sign this contract within 30 days, we can hold material and forgo this cost.**

Rev. Ben Heimach-Snipes  
Roofing & Solar Consultant  
317-361-3091  
benh@covenantsolarroof.com  
covenantsolar.com

